

US 41 ROAD RECONSTRUCTION



Location:
Sullivan County, Indiana

Owner: INDOT

Client: INDOT

Construction Cost:
\$40,000,000

Completion Date: 2006

Project Description

This project involved pavement reconstruction and rehabilitation of US 41 from the town of Carlisle to the town of Shelburn in Sullivan County. The 14 mile long, dual lane divided highway project involved over 13 miles of pavement rehabilitation/rubblization including about 1 mile of pavement replacement at the SR 154 intersection in Sullivan. Right and left turn lanes were either added or lengthened at fourteen intersections within the project limits. JSE inspected over 50 pipe structures crossing under US 41. We made recommendations whether to rehabilitate or replace the structures. The project included the rehabilitation of four sets of twin bridges. All the bridges were simple bridge rehabilitations and deck overlays. A new traffic signal at the SR 154 intersection and flashing beacons were added at several intersections. JSE provided project management, utility coordination, maintenance of traffic, road, bridge, drainage and traffic design services for this \$40,000,000 reconstruction project. JSE completed the design phase in less than three years

Project Data:

Total Length: 14 miles
Time to Complete Plans: 3 years
Number of Bridges: 4 Bridge Rehabs